

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20358-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 2-13S-16W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: BOXBERGER Well #: 3  
County: ELLIS Total Vertical Depth: 3464 feet

Operator License No.: 5145  
Op Name: DREILING OIL INC  
Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	184	0	125 SX
PROD	4.5	3463	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2010 7:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TERRY W. PIESKER Company: DREILING OIL INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 670 sxs 60/40 pozmix- 4% gel - 800# hulls.  
04/21/1989 - Squeeze holes at 2020'-2050'; 2804'-2835' w/150 sxs.  
PBTB 3416'.  
Operator elected all cement plug.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/14/2010 1:35 PM KCC Agent: PAT STAAB

Actual Plugging Report:

L.K. Wireline perfed at 1120' - 550' - 180' with two shot perf.  
Express Well Service RIH with tubing to 3276'.  
Allied rigged to tubing and pumped 150 sxs with 250# hulls mixed in.  
Pulled tubing to 1650' - Allied rigged to tubing and pumped 210 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 825' - Allied rigged to tubing and pumped 100 sxs cement with 150# hulls mixed in.  
Ordered more cement. Pumped an additional 180 sxs cement with 400# hulls to circulate cement up 4 1/2" casing.  
Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 25 sxs cement.  
Max. P.S.I. 100#. S.I.P. 100#.  
Rigged to 8 5/8" casing and pumped 5 sxs cement.  
Max. P.S.I. 100#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3353	3358		
3331	3334		
3285	3287		
2804	2835		
2020	2050		

RECEIVED  
JUN 17 2010  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #41717.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

CM

H. B. MABEE CO. #3 BOXBERGER 2-13-16W  
 OKLAHOMA CITY, OKLA. SW SE NW  
 Contr. L. J. DRELLING & SONS Cty. ELLIS  
 Geol. FRANCIS WHISLER Pool SEITZ EXT  
 E. 1985 KB Cm. 11/26/68 Cp. 1/16/69 IP PMP 103 BOPD, NW/  
 LANS 3287-3358


API 15-051-20,358

LOG Tops	Depth	Datum	Csg.
ANH	1104	+ 891	8" 184/125 SX; 4 1/2" 3463/150 SX
TOP	2927	- 932	DST 3152-3204/1', 125' WM, BHP
HEEB	3146	-1151	1232-1068#/30", FP 98-112#
TOR	3166	-1181	DST 3204-54/1', 840' W, BHP 629-
LANS	3198	-1213	605#/30", FP 96-485#
BKC	3438	-1453	DST 3319-69/1', 150' GIP, 150' OCM
ARB	3454	-1469	BHP 217-176#/30", FP 40-152#
LTD	3464	-1479	DST 3366-3414/1', 305' MUD, FBHP
RTD	3464	-1479	443#/30", FP 258-258#
			DST 3456-64/1', 5' M, FBHP 12#/30"
			FP 12-12#
			CO PF 20/3353-58, 12/3331-34, 8/
			3285-87, A 5000, SWB LD & SWB
			12-15 BOPH, NW, POP
			NO CORES

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS