

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-051-20940-00-00  
 Spot: N2SENESE Sec/Twnshp/Rge: 10-12S-16W  
1650 feet from S Section Line, 330 feet from E Section Line  
 Lease Name: DICKINSON Well #: 7-A  
 County: ELLIS Total Vertical Depth: 3350 feet

Operator License No.: 5145  
 Op Name: DREILING OIL INC  
 Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3310		
SURF	8.625	154	0	175 SX
PROD	5.5	3349	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/10/2010 2:30 PM  
 Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
 Proposal Rcvd. from: TERRY W. PEISKER Company: DREILING OIL, INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls - 9 sxs gel spacer.  
 Cast iron bridge plug at 3310'.  
 Squeezed 2097' and 564' w/200 sxs; 2051' to 2082' w/150 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 06/10/2010 7:00 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Ran tubing to 3200' - pumped 9 sxs gel spacer - followed with 75 sxs 60/40 pozmix - 4% gel.  
 Pulled tubing to 1800' - pumped 180 sxs 60/40 pozmix - 4% gel to circulate to surface.  
 Pulled all tubing. Topped off 5 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.  
 06/11/2010 - Hooked to 8 5/8" x 5 1/2" annulus. Pumped 15 sxs 60/40 pozmix - 4% gel.  
 S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
3286	3290		
3269			
3219			
3198			
3151	3158		
3082	3086		
3060	3064		
2786	2790		

*6/21/10*  
*2010061250*

Remarks: ALLIED CEMENTING COMPANY-TICKETE #41716.

Plugged through: TBG

District: 04

Signed Pat Bedore  
 (TECHNICIAN) CM

RECEIVED

JUN 15 2010

KCC WICHITA

JUN 11 2010

DREILING OIL, INC.

#7-A DICKINSON 10-12-16W  
75'N, SE NE SE

RT. 2, VICTORIA, KS.  
CONTR. CO. TOOLS

CTY. ELLIS

GEOL. DICK GREEN

FIELD BLUE HILL

1847 KB 2/28/74 CARD 7/11/74 IP P 27 BOPD + 30% W  
ISSUED

LANS 3151-58 & 3286-90

+	+	+
+	+	+
+	+	+

API 15-051-20,940

SMP	TOPS	DEPTH	DATUM
SC		999	- 848
B SC		1033	- 814
TOP		2734	- 887
HEEB		3005	-1158
TOR		3026	-1179
LANS		3055	-1208
BKC		3301	-1454
CONG		3329	-1482
ARB		3349	-1502
TD		3350	-1503
DD TD		3386	-1539

8-5/8" 154/75SX, 5 1/2" 3349/175SX

NO LOG

NO DST'S

CO & DD 3386, NS, PB 3300, PF (LANS)  
16/3286-90, 20/3151-58, A 1500, REC  
LD, SWB 5BFPH 30% OIL, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS