

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22777-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 14-12S-16W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SMITH Well #: 7  
County: ELLIS Total Vertical Depth: 3432 feet

Operator License No.: 5145  
Op Name: DREILING OIL INC  
Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 167        | 0           | 130 SX   |
| PROD   | 5.5   | 3431       | 0           | 150 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2010 2:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: TERRY W. PIESKER Company: DREILING OIL INC. Phone: (785) 625-8327

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Shoot perfs at 1650' and 1025'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/11/2010 5:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perfs at 1650' and 1025'.  
Ran tubing to 3270' - pumped 150 sxs cement.  
Pulled tubing to 1650' - pumped 160 sxs cement - good circulation.  
Pulled tubing out - tied onto 5 1/2" casing - squeezed with 15 sxs.,  
S.I.P. 200#. Tied onto backside - full.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3379 | 3382 |      | CIBP     |

6/24/10  
2010061250

RECEIVED  
JUN 17 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #33739.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

JUN 15 2010

replacement card

DREILING OIL  
VICTORIA KS

14-12S-16W  
SW SE SW

# 7 SMITH A

site: 2-1/2 S & 1-3/4 W OF FAIRPORT KS  
cont: DREILING OIL

cty: ELLIS  
field: BLUE HILL

API 15-051-22777

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

|               |               |               |                 |                  |
|---------------|---------------|---------------|-----------------|------------------|
| tr            | spd           | drig          | card            | last             |
| date 12/21/81 | date 12/15/81 | comp 12/21/81 | issued 07/08/82 | revised 08/18/97 |

ELV: 1873 KB, 1868 GL  
 tops.....depth/ datum  
 RTD.....3432 -1559  
 NO TOPS RPTD

**IP status:**  
 OIL, ARB, INTV NA, 05/15/82  
 INFO REL: 8/18/97 - WAS OIL WELL - TEMP COMP  
 NOTE: CORR 7/8/82 - ORIG FR AS # 7 SMITH  
 CSG: 8-5/8" 167, PROD CSG NA, DV TOOL USED (DEPTH NA)  
 NO CORES OR DSTS RPTD  
 MICT - CO, PF (ARE) INTV NA, GSO, POP, OIL WELL (POTENTIAL NOT RPTD), 5/15/82 - NO OTHER INFO RELEASED BY OPERATOR OR ON KCC RECORDS; ALL REQUESTS FOR INFO DENIED

COPYRIGHT 1997  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS