

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20821-00-00  
Spot: S2SWSWSW Sec/Twnshp/Rge: 9-34S-23W  
180 feet from S Section Line, 330 feet from W Section Line  
Lease Name: EUBANK - B Well #: 9  
County: CLARK Total Vertical Depth: 5750 feet

Operator License No.: 33392  
Op Name: KEITH F. WALKER OIL & GAS CO., LLC  
Address: 219 STANLEY ST PO BOX 1725  
ARDMORE, OK 73401

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5369		WITH 10 SX CMT
SURF	13.38	270		WITH 325 SX CMT
COND	20	120		WITH 12 YDS CMT
I1	8.625	834		WITH 500 SX CMT
PROD	4.5	5739	2183	WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/03/2010 9:30 AM  
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.  
Proposal Rcvd. from: RIGO MONDRANO Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 435-3373

Proposed Plugging Method: CIBP @ 5369' WITH 10 SX CMT. PLUG AT 870' WITH 15 SX GEL, 200# HULLS & 75 SX CMT. PLUG AT 240' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/03/2010 10:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5369' WITH 10 SX CMT. 1ST PLUG LOAD HOLE WITH GEL WATER. PUMP 200# HULLS & 75 SX CMT AT 870'. 2ND PLUG AT 240' WITH 40 SX CMT. 3RD PLUG AT 30' WITH 10 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5446	5448		
5436	5444		

6/21/10  
2010061254  
RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 14 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED COMMON CEMENT BY PHIL DOLLARD OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
JUN - 9 2010  
KCC DODGE CITY

Signed

Jerry W. Stapleton  
PLUGGER (TECHNICIAN)

Form CP-125