

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21343-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 13-15S-12W  
2310 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: HEINZE A Well #: 2  
County: RUSSELL Total Vertical Depth: 3378 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	202	0	w/200 sxs cmt
PROD	4.5	3366	0	w/200 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2010 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: \_\_\_\_\_ Company: GLM COMPANY Phone: (785) 483-1307

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 06/11/2010 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Drilled to 2462' with pump and power swivel.  
Stopped making progress. POOH.  
Perforated at 740' and 200'.  
Ran tubing to 2450'.  
Pumped 125 sxs 60/40 pozmix - 4% gel cement.  
Pulled to 1220' and pumped 175 sxs cement - ran out of cement.  
Got more cement and pumped 50 sxs - circulated inside and out. POOH.  
Tied onto casing. Max. P.S.I. 400#.

6/21/10  
2010061258

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

RECEIVED

JUN 15 2010

KCC WICHITA

JUN 14 2010

R & H OIL & GAS, INC. REPLACEMENT CARD: 13-15-12W  
 54 S. KANSAS #2 HEINZ "A" NE NW SE  
 RUSSELL, KS.

CONTR BERGMAN DRILLING CO. CTY RUSSELL

GEOL \_\_\_\_\_ FIELD DRISCOLL

E 1879 KB CM 10/9/79 CARD ISSUED 5/9/79 IP P 9 BOPD, TR WTR  
LKC-INTV NA

+	+
+	+

API 15-167-21,343

LOG	TOPS	DEPTH	DATUM
TOP		2680	- 801
HEEB		2928	-1049
TOR		2946	-1067
DOUG SD		2974	-1095
BR LM		3018	-1139
LKC		3029	-1150
B KC		3289	-1410
CONG SD		3324	-1445
ARB		3366	-1487
RTD		3378	-1499
LTD		3379	-1500
DDTD		3396	-1517

8-5/8" 202/200sx, 4 1/2" 3366/200sx  
 NO DST'S  
 MICT - CO, (ARB OH), DD 3396 TD,  
 HFW, SET BP, PF (LKC), ACIDIZED, POP  
 NO OTHER INFO TO BE RELEASED BY  
 OPERATOR

INFO RELEASED: RELEASED TOPS

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS