

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20188-00-00  
Spot: NWNWNWSE Sec/Twnshp/Rge: 23-29S-17W  
2434 feet from S Section Line, 2543 feet from E Section Line  
Lease Name: ANCHOR D Well #: 2  
County: KIOWA Total Vertical Depth: 2835 feet

Operator License No.: 3581  
Op Name: RED OAK ENERGY, INC.  
Address: 7701 E KELLOGG DR STE 710 PO BOX  
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2700		WITH 2 SX CMT
SURF	8.625	263		WITH 250 SX CMT
PROD	5.5	2834	1290	

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/08/2010 9:00 AM  
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC  
Proposal Rcvd. from: BRIAN SIROKY Company: AMERICAN WELL SERVICE LLC Phone: (620) 770-0621

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. PLUG AT 880' LOAD HOLE WITH GEL WATER & SPOT 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/08/2010 12:05 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2700' WITH 2 SX CMT. 1ST PLUG AT 879' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 35' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2771	2775		

6/21/10  
2010061263

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 14 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED

JUN - 9 2010

KCC DODGE CITY

Form SP-263