

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-27813-00-00  
Spot: SWSWSENE Sec/Twnshp/Rge: 27-30S-16E  
2446 feet from N Section Line, 1305 feet from E Section Line  
Lease Name: WEST Well #: A5  
County: WILSON Total Vertical Depth: 900 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

| String | Size | Depth (ft) | Pulled (ft) | Comments  |
|--------|------|------------|-------------|-----------|
| SURF   | 7    | 22         |             | 10 SX CMT |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2010 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: REX ASHLOCK Company: COLT ENERGY, INC Phone: (620) 365-3111

Proposed  
Plugging  
Method:

Run cement string to TD and plug well utilizing gel spacers and cement plugs at TD, 700', and 250' to surface.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 03/05/2010 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Ran drill pipe to 900' and then pumped 25 sacks of portland cement. Pulled pipe to 700' and then pumped 10 sacks of portland cement. Pulled pipe to 250' and then pumped 80 sacks of portland cement. A total of 115 sacks of portland cement were used to plug well. Gel spacers were utilized between cement plugs.

Perfs:

RECEIVED

JUN 11 2010

AMD

KCC Chanute Dist. #3

6/22/10  
2010061270

RECEIVED

JUN 11

KCC WILSON

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)