

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

Drilled April 1947

API NUMBER 15-167-01729-0000 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR BP Exploration INC. OPERATORS LICENSE NO. 06854

ADDRESS P.O. Box 4587 Houston Tx. 77210 PHONE # (713) 552-8500

LEASE (FARM) Whitson WELL NO. 2 WELL LOCATION E/2 SW SW COUNTY Russell

SEC. 16 TWP. 11S RGE. 15 ~~(E/2) (W)~~ TOTAL DEPTH 3350' PLUG BACK TD 3248'

Check One:

OIL WELL XXXX GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 953' CEMENTED WITH 560 SACKS

CASING SIZE 5 1/2" SET AT 3338' CEMENTED WITH 175 SACKS

PERFORATED AT 2899-2904' (Topeka) 2988-3210' (L-KC)

CONDITION OF WELL: GOOD XXX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1) Set retainer at 2850', squeeze perforations with 100 sx 65-35 Pozmix, spot 10 sx of cement on top of retainer; 2) shoot squeeze holes at 1000' in 5 1/2" casing, attempt to establish circulation to surface via 8 5/8" X 5 1/2"

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
11-13-89 (If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN NOV. 27, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Joel Stull - field supervisor PHONE # (913) 637-5290

ADDRESS Gorham, Ks. 67640

PLUGGING CONTRACTOR Halliburton Services LICENSE NO. 5287

ADDRESS 1100 East 8th St. Hays, Ks. 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Joanne Presko
(Operator or Agent)

DATE: 11-10-89

(4)

2) annulus. If successful, set retainer at 950', circulate 125 sx Pozmix into annulus. Spot 10 sx on top of retainer. If unable to circulate fluid to surface, spot 10 sx across squeeze holes; attempt to pump down annulus. If successful, pump 125 sx down annulus. 3) Spot 10 sx surface plug. 4) Cut casing below plow depth, weld on steel plate.

Note: 1) 9.0 ppg mud (36 cp viscosity) will be placed between cement plugs.

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

FEB 13 1990

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

November 13, 1989

**NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION**

BP Exploration, Inc.
P.O. Box 4587
Houston, TX 77210

Whitson 2
E/2 SW SW
16-11-15W
Russell County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Director

District: #4 2301 e. 13thHays, KS 67601(913) 628-1200