

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 36-43

LOCATION Sw-nw-ne

SEC. 16 TWP. 11 RGE. 15W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Howe

Operator Sterns Petr. Inc. Address Box 313 Russell Kans

Field _____ County Russell

Total Depth 3446 Feet.

Plugging Contractor Barnes & Son

Plugging Contractor's License No. 9

Address Russell Kans

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 1/2" @ 250 C.W.C. 5 1/2" set 3396 w/ 50
sf Cem. 4 1/2" liner set 3359' to 3446' Top perf 3421
Filled hole back with sand to 3374' and
dumped 5 sf Cem. Shot off and pulled 5 1/2" casing
Filled hole with mud to 250' set rock
bridge and run 20 sf Cem. mud to 35'
rock bridge and 10 sf Cem to base of cellar

PLUGGING
FILE SEC 16 T 11 R 15W
BOOK PAGE 36 LINE 43

6-24-54
CONSERVATION DIVISION
Wichita, Kansas

Warren H. Horner
District Conservation Agent

Date June 22, 1954