

15-167-00142-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 145-40

LOCATION SWe NE¹/₄ - SW¹/₄

SEC. 16 TWP. 11 RGE. 15 W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 4 Lease Whitson

Operator Summit Oil Co. Inc. Address Box 73 Russell Kans.

Field _____ County Russell

Total Depth 3382 Feet.

Plugging Contractor Jayhawk Casing Pulling Co.

Plugging Contractor's License No. 19

Address Russell Kans

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8³/₈ @ 185' C.W.C. Oil string 5¹/₂" @ 3370'
w/ 100 sx cem. Filled back with sand to 3360' and
dumped 5 sx cem. with dump bailer. Shot off and
pulled 5¹/₂" casing. Filled hole with heavy mud
to 185' set rock bridge and mixed and run
25 sx Cem. mud to 35' rock bridge and 10 sx of
Cem. to base of cellar.

PLUGGING
FILE SIX 16 T 11 R 15 W
BOOK PAGE 145 LINE 10

1-13-54
DISTRICT CONSERVATION AGENT
Wichita, Kansas

Warren H. Horner
District Conservation Agent

Date 1-11-54