


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County, Sec. 7 Twp. 11 Rge. 15 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE-SE-NW
Lease Owner Leo J. Dreiling Oil Company
Lease Name Albrecht Well No. 1
Office Address Route 2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-21 19 67
Application for plugging filed 6-21 19 67
Application for plugging approved 6-21 19 67
Plugging commenced 6-21 19 67
Plugging completed 6-21 19 67
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	164'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st. plug was set using 20 sacks cement and 1/4 sack hulls. Filling hole with rotary mud to a depth of 160' where 2nd. plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 40' where 3rd. plug was set using 8 sacks cement and 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
6-27-67
JUN 27 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 67

My commission expires September 19, 1970
Joseph A. Hess
JOSEPH A. HESS Notary Public.

15-167-20070-0000

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Route 2, Victoria, Kansas 67671	Sec. 7	Twp. 11	Rng. 15
Farm	Albrecht No. 1	Location	SE-SE-NW	
Total Depth	3550'	County	Russell	
Comm.	6-14-67	Comp.	6-21-67	
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671	Elevation:	1916'	K.B.
	Casing Record		1913'	D.F.
	164' 8 5/8"		1911'	G.R.
	Cement Record	Production:	D & A	
	80 sacks cement			

Figures Indicate Bottom of Formations

0'	60'	Top Soil & Clay
60'	162'	Shale
162'	375'	Shale & Hard Sand Streaks
375'	415'	Sand
415'	485'	Shale
485'	580'	Sand
580'	1035'	Redbed & Shale
1035'	1089'	Redbed & Shale
1089'	1121'	Anhy.
1121'	1640'	Shale & Shells
1640'	1705'	Shale & Lime
1705'	2015'	Shale & Lime
2015'	2108'	Shale & Lime
2108'	2233'	Shale & Lime
2233'	2380'	Shale & Lime
2380'	2516'	Shale & Lime
2516'	2745'	Shale & Lime
2745'	2901'	Shale & Lime
2901'	2978'	Lime & Shale
2978'	3037'	Lime
3037'	3129'	Lime
3129'	3189'	Lime
3189'	3260'	Lime
3260'	3317'	Lime
3317'	3424'	Lime
3424'	3513'	Lime & Chert
3513'	3550'	Lime & Shale
3550'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1967
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Albrecht #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 26th day of June 1967.

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970