

15-167-22125-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Russell SEC. 7 TWP. 11 RGE. 15 E/W  
 Location as in quarters or footage from lines:  
NW/4 1765' FNL 3540' EEL


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Graham-Michaelis Corporation  
 Lease Name Elliott Well No. #5-7  
 Office Address Box 247 Wichita, Kansas 67201  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 5-28-83  
 Application for plugging filed 5-28-83  
 Plugging commenced 5-28-83 7:15 am  
 Plugging completed 5-28-83 11:00 am  
 Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well David Wann  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3490  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out


Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

- Filled hole to 1080 with heavy mud and mixed 20 sacks of cement and pumped in hole thru drill pipe.
  - Filled hole to 535 with heavy mud and mixed 80 sacks of cement and pumped in hole thru drill pipe.
  - Filled hole to 330 with heavy mud and mixed 40 sacks of cement and pumped in hole thru drill pipe.
  - Filled hole to 40' build solid bridge pushed sown plug and mixed 10 sacks of cement and filled hole to bottom of cellar; mixed 10 sacks and pumped into the rat hole.
- All cement used was 50-50 Poz Mix 4% gel 3% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revlin Drlg., Inc.

STATE OF Kansas COUNTY OF Russell, ss.  
Stanley C. Lingreen (employee of owner) or ~~(owner)~~ of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.



(Signature) Stanley C. Lingreen  
Box 203 Russell, Kansas  
 (Address) 67665

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1983

My Commission expires: November 10, 1984  
Paula J. Gibson  
 Notary Public.

RECEIVED  
 STATE CORPORATION COMMISSION

JUN 10 1983