

15-167-20579-0000

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1973

CONSERVATION DIVISION CP-4
Wichita, Kansas


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Russell County Sec. 7 Twp. 11S Rge. 15W (E) (W)
Location as "NE, CNWASW" or footage from lines SE NW NW
Lease Owner Clinton Oil Company
Lease Name Meta Albrecht Well No. 1-V
Office Address 217 North Water, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed March 7, 19 73
Application for plugging filed March 7, 19 73
Application for plugging approved March 7, 19 73
Plugging commenced March 7, 19 73
Plugging completed March 7, 19 73
Reason for abandonment of well or producing formation D&A



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3543 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	221'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Plugged hole by Sun w/50-50 pozmix
4% total gel - 50 sx @ 600' 30 sx @ 200'
Hulls & plug @ 30' w/15 sx to surface

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

State of Kansas County of Sedgwick
Gloria Fawcett (duplicate of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, cements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of March, 19 73



Virginia K. Albert
Notary Public.

My commission expires July 23, 1974

15-167-20579-0000

DRILLERS LOG

No. 1-V Meta Albrecht

CASING RECORD:

10 3/4" @ 221'
w/200 sx cement

COMPANY:

Clinton Oil Company

CONTRACTOR:

Red Tiger Drilling Company

COMMENCED:

February 26, 1973

COMPLETED:

March 7, 1973

DESCRIPTION:

SE NW NW
7-11S-15W
Russell County,
Kansas

TOTAL DEPTH: 3543'

ELEVATION

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil & post rock	0	80	
Shale & hard rock	80	160	
Shale & rock	160	223	
Shale	223	305	
Sand	305	415	
Shale & Sand strings	415	595	
Shale & sand & red bed	595	1072	
Anhydrite	1072	1106	
Shale	1106	1700	
Shale & lime strings	1700	1968	
Lime	1968	2100	
Lime & shale	2100	2870	
Lime	2870	3385	
Lime & Congl.	3385	3488	
Lime	3488	3543	

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 9th day of March, 1973.



Virginia K. Albert
Notary Public

My Commission Expires: July 23, 1974