


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
311 No. Broadway  
Wichita, Kansas

Russell County, Sec. 7 Twp. 11S Rge. 15 (E) W(W)

Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Helmerich & Payne, Inc.  
Lease Name Albrecht Well No. 1  
Office Address First National Building, Tulsa 3, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 9 19 61  
Application for plugging filed July 9 19 61  
Application for plugging approved July 9 19 61  
Plugging commenced July 9 19 61  
Plugging completed July 10 19 61  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3758' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	261'	8-5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3758' to 250' - Heavy rotary Mud  
250' to 173' - 1/4 sack hulls, plug & 25 sacks cement  
173' to 35' - Heavy rotary mud  
35' to 6' - 1/4 sack hulls, plug & 10 sacks cement  
6' to surface - cellar

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PEEL BROTHERS, INC.  
Address P. O. Box 359 Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Peel Brothers, Inc. (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY [Signature]  
P. O. Box 359, Hoisington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of July, 19 61

My commission expires April 27, 1964

[Signature]  
Notary Public.

INVOICED  
DATE 7/18/61  
INV. NO. 3346-W

## DRILLER'S LOG

Well Owner:	Helmerich & Payne, Inc.	NE NE NE
Farm Name:	Albrecht Well No. 1	Sec. 7, Twp. 11S, Rge. 15W
Commenced:	6/28/61	
Completed:	7/10/61	County: Russell,
Total Depth:	3758'	Kansas
Casing:	8 5/8" @ 261' cem.	Elevation:
Contractor:	Peel Brothers, Inc.	Production: Dry

Figures below indicate bottoms of formations:

Clay	20
Post rock	60
Shale	265
Shale & shells	670
Sand & pyrite	765
Lime	770
Sand & shale	990
Red bed	1355
Lime	1405
Shale	1810
Lime, shale streaks	1920
Lime & shale	2210
Lime	2285
Shale	2300
Lime & shale	2410
Lime & shale	2510
Shale & shells	2655
Lime & shale	2870
Broken Lime	3015
Lime	3105
Lime & shale	3155
Lime	3590
Cherty lime, conglomerate	3675
Conglomerate	3758
Total Depth	3758

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: *Jack Mattent*

SUBSCRIBED AND SWORN to before me this 10 day of July, 1961.

My commission expires: April 27, 1964

*Ruth Bruck*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1961

CONSERVATION DIVISION  
Wichita, Kansas