

15-169-00179-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Saline County, Sec. 29 Twp. 13S Rge. 2W (E) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C. NW NW  
Lease Owner Francis Oil & Gas, Inc.  
Lease Name Schippel Well No. 1  
Office Address 908 Palace Bldg. Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 7, 1959 19  
Application for plugging filed May 7, 1959 19  
Application for plugging approved May 7, 1959 19  
Plugging commenced May 7, 1959 19  
Plugging completed May 7, 1959 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3135 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	223 w/110 sacks	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug at 210' with 1/2 sack hulls, 20 sacks cement; mud to 40'.  
Set plug at 40' with 1/2 sack hulls, 10 sacks cement. Cement to surface.  
Cemented rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1959  
08-25-1959  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Veeder Supply and Development Co.  
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.  
C. H. Woods (employee of owner) or \_\_\_\_\_ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods  
Cherryvale, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 1959

My commission expires July 11, 1960

Loles Lawson  
Notary Public.

PLUGGING  
FILE SEC. 29 T. 13 R. 2W  
BOOK PAGE 60 LINE 31

13-169-00179-00-00

Veeder Supply & Dev'l. Co.

Cherryvale, Kansas

Francis Oil & Gas Inc., Herman Geo. Kaiser

Drilled for and Veeder Supply & Development Co. Farm Schippel Nol Depth 3135

Contractor Veeder Supply and Development Co. Pipe 223' 8 5/8" csg. w/140 sacks

Location C. NW NW Sec. 29 Twp 13S Range 2W

Commenced 4-28-59 Completed 5-7-59 County Saline State Kansas

Cellar	0	9	9
Shale	9	60	51
Sand shale	60	155	95
Shale	155	223	68
Lime w/shale streaks	223	402	179
Shale w/lime streaks	402	500	98
Lime	500	580	80
Shale w/lime streaks	580	590	10
Shale and lime	590	610	20
Lime	610	710	100
Shale w/lime streaks	710	900	190
Lime w/shale streaks	900	1080	180
Shale w/lime streaks	1080	1380	300
Shale and lime	1380	1730	350
Lime and shale	1730	2066	336
Lime	2066	2381	315
Lime and shale	2381	2675	294
Shale and lime	2675	2752	77
Miss. Lime	2752	2905	153
Lime and shale	2905	3135	230
T. D.	3135		

Abandoned.

RECEIVED  
 STATE CONSERVATION COMMISSION  
 AUG 25 1959  
 08-25-1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS )  
Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Schippel #1 well located in Section 29-13S-2W. Saline County, Kansas, and the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By C. H. Woods  
C. H. Woods

Subscribed and sworn to before me this 14th day of May, 1959.

Loles Hansen  
Notary Public

My Commission Expires Wuly 11, 1960.

PLUGGING  
 FILE SEC 29, 3 R. 2W  
 BOOK PAGE 60 LINE 31