

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-167-36586-0000

API NUMBER 3-1933

LEASE NAME Hines A

WELL NUMBER 1

         Ft. from S Section Line

C NW ¼ NW Ft. from E Section Line

SEC. 16 TWP. 11 RGE. 15 (E) or (W)

COUNTY Russell

Date Well Completed 3/1933

Plugging Commenced 12-5-90

Plugging Completed 12-12-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-12-90 (date)

by Hays Office Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	1013	12 1/2"		None
	Casing	0	2192	10		None
		0	2692	8 1/2"		None
		0	3212	7		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each set. Poor boy 10" to 7" leave 20" open. Perf. 2 holes at 1020' and 2 at 525'. Run tubing to 3115 Pump 200 sk. cement. Pull tubg. to 1350' Circulate 150 sk. cement. Pull tubg. 10" won't circ Perf. 2 holes at 250'. Circ 200 sks. cement in 10" Close in 10" had returns on 20". Run tubg. in 20". Tag 100'. Pull tubg. run in 7" tag 800 slurry cement at 150'. Pull tubg. Run (If additional description is necessary, use BACK of this form.)

tbq. in 20". Pump 50 sk. in 7". Pump 125 sk. down 2" tubg. between 7" and 15". Cement cir

Name of Plugging Contractor Okmar Oil Company License No. 5245  
 Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Okmar Oil Company

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, KS 67601

NOTARY PUBLIC  
 STATE OF KANSAS  
 MY APPT. EXP. MAY 1, 1991

SUBSCRIBED AND SWORN TO before me this 12 day of December, 19 90

DEC 13 1990

Rosemary Smith  
 Notary Public

My Commission Expires: 5-1-1991