


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Russell County, Sec. 16 Twp. 11 Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines S.1/2, NE.1/4, S.1/2
Lease Owner Summit Oil Co., Inc.
Lease Name Whitson Well No. 4
Office Address Box 71, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 12, 19 53
Application for plugging filed November 26, 19 53
Application for plugging approved November 30, 19 53
Plugging commenced January 7, 19 54
Plugging completed January 11, 19 54
Reason for abandonment of well or producing formation Dry hole.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, P.O. Box 207, Great Bend, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Anhydrite				8 5/8"	185.54	None
Anhydrite		986	1014			
Arbuckle		3361	3363	5 1/2"	3370.30	2494'
(8 5/8" casing cemented with 125 sks. 5 1/2" casing, 3370.30' cemented with 125 sks.)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1-7-54 Rig up. Clean out cellar. Fill hole with sand from 3380ft. 3360 ft. dumped 5 sks cement set sills and jacks. Work pipe to 25 in. tention.
1-8-54 Shooting and working pipe 1st shot 2584 ft. 2nd shot 2523 ft. 3rd shot 2492 ft. Pipe loose
1-11-54 Filled hole with mud to 185 ft. Put in 10 ft. rock bridge mixed and run 20 sks cement. Filled hole with mud from top of cement at 125 ft. to 35 ft. Put in 5 ft. rock bridge. Mixed and run 10 sks cement. Filled to top of surface pipe. Pulled 2494 ft. of pipe.

2-23-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jayhawk Casing Pulling Company
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Oscar Ostrum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Summit Oil Co. By Oscar Ostrum
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 54.

Luella Beyer
Notary Public.

My commission expires 2-8-56

