
# STATE OF KANSAS STATE CORPORATION COMMISSION CONSERVATION DIVISION 200 Colorado Derby Building Wichita, Kansas 67202

#### WELL PLUGGING APPLICATION FORM

(File One Copy)

Drilled May 1949

(This must be listed; if no API# was issued, please	note drilling completion date.)
LEASE OPERATOR  BP Exploration, Inc.  R. O. Poy 4597 Houston Tv. 77310	OPERATORS LICENSE NO. $06854$
ADDRESS P.O. Box 4587 Houston, Tx. 77210	PHONE # (713) 552-8500
Chrisler B 1	TOTAL PROPERTY PUSSED I
LEASE (FARM) WELL NO. 1 WELL LOCA	COONTY RUSSETT
SEC. TWP. 11S RGE. 15 XEXXX (W) TOTAL DEPTH 3	PLUG BACK TD 3361'
Check One:	
OIL WELL XXX GAS WELL D&A SWD or INJ W	ELL DOCKET NO
SURFACE CASING SIZE $\frac{13 \ 3/8"}{}$ SET AT $\frac{145"}{}$ CEM	
CASING SIZE $\frac{5 \cdot 1/2"}{}$ SET AT $\frac{3414'}{}$ CEM	ENTED WITH 125 SACKS
	ENIDO HAM
PERFORATED AT 3106-3297' L-KC	
CONDITION OF WELL: GOOD XXX POOR CASING LE	AK JUNK IN HOLE
OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1) Set	retainer at 3000', squeeze perforations
with 100 sx 65-35 Pozmix; 2) Spot 10 sx cement on top of	
13 3/8" X 5-1/2" annulus, if successful pump 130 sx Pozmi	x down annulus; 4) Perforate casing at
(If additional space is needed us	
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YE	IS ACO-1 FILED?
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Ye (If not, explain)	ED
DATE AND HOUR PLUGGING IS DESIRED TO BEGIN NOV. 21, 19	989
PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH	I K.S.A. 55-101 et seg AND THE RULES AND
REGULATIONS OF THE STATE CORPORATION COMMISSION (State of Particles of Particular of P	ਸ਼ਸ਼ਸ਼ ਹਿਸਤ ਸ਼ਬਮਾਂ
NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE	OF PLUGGING OPERATIONS:
Joel Stull -field supervisor	PHONE # (913) 637-5290
ADDRESS Gorham, Kansas 67640	
PLUGGING CONTRACTOR Halliburton Services	LICENSE NO. 5287
ADDRESS 1100 East 8th St. Hays, Kansas 67601	PHONE # (913) 625-3431
PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED:	: Opanne Kresto
	(Operator or Agent)
$(\checkmark)$ DATE:	11-10-89



Note: 1) 9.0 ppg mud will be placed between cement plugs

2) Drillers report shows top of anhydrite @ 1033'.

## 15-167-01704-0000

### State of Kansas



## Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

THIS NOTICE

FEB 1 3 1990

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

#### **EXPIRES**

November 13, 1989

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

BP Exploration, Inc. P.O. box 4587 Houston, TX 77210

Chrisler B 1 NE NW SW Sec. 09-11-15W Russell County

#### Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht Director

District:	#4	2301 E. 13th	
		Hays, KS 67601	
		(040) (00 4000	
		(913) 628-1200	