

15-167-06576-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 6-22-1940  
LEASE NAME Durham B  
WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Line  
C W<sub>2</sub> NE NE Ft. from E Section Line  
SEC. 20 TWP. 11 RGE. 15 (E) or (W)  
COUNTY Russell  
Date Well Completed 6-22-1940  
Plugging Commenced 7-31-90  
Plugging Completed 7-31-90

LEASE OPERATOR Okmar Oil Company  
ADDRESS Box 723 Hays, Kansas 67601  
PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-31-90 (date)  
by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3360

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD **AUG - 3 1990**

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	964	10"		None
	Casing	0	2693	8 5/8"		None
			3100	7"		None
			3001	5 1/2"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Clean out to 929'. Mix 260 sks. 65/35 pos, 10% gel, cement circulated to surface on 7". Got out 9 joints tubing. Hook to 7" Mix 25 sks. 65/35 pos, 10% gel. Circulated out surface. Shut in surface casing. Mix 315 sks. 65/35 pos, 10% gel, 200# hulls down 7" to squeeze. Pressure 400#. Shut in pressure 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723 Hays, Kansas 67601 BJ Services (cement)


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Okmar Oil Company

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, KS 67601



SUBSCRIBED AND SWORN to before me this 2 day of August, 19 90

Foreman J. Smith  
Notary Public

My Commission Expires: 5/1/1991