


15-167-04544-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

R
WELL PLUGGING RECORD

Russell County. Sec. 22 Twp. 11 Rge. 15W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Womer Oil Company
Lease Name Bowlus Well No. 1
Office Address Box 996, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 11/1 1959
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 11/1 1959
Plugging completed 11/2 1959
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	970'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Heavy mud was pumped into well - 10 sx of cement were spotted @ 800' in well, 170' above bottom of 8 5/8". A steel cap was then screwed into top of 8 5/8".

RECEIVED
FEB 11 1960

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Dunne-Gardner Drilling Co., Inc.
Address 300 Schweiter Building

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Glen Rupe (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen Rupe
Box 996, Wichita 1, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of February 1960.

My commission expires 7/19/62
Delbert D. Parker Notary Public.



15-167-04544-0000

CONTRACTOR'S WELL LOG

COMPANY: Womer Oil Company,
434 Ohio
Wichita, Kansas

LEASE: Bowlus

WELL: No. 1

LOCATION: NE NE SE Section 22, Township 11 South,
Range 15 West, Russell County, Kansas

CONTRACTOR: Dunne-Gardner Drilling Co., Inc.
300 Schweitzer Building
Wichita, Kansas

DATE COMMENCED: October 21, 1959

DATE COMPLETED: November 1, 1959

TOTAL DEPTH: 3377 Feet

CASING: 943' - 8 5/8" surface casing with 500
sacks cement 2% c.c.

<u>FROM:</u>	<u>TO:</u>	
0	95	Clay & Shale
95	450	Shale & Shells
450	560	Sand & Shale
560	920	Shale, Shells & Red Bed
920	960	Anhydrite
960	1520	Shale & Shells
1520	2530	Lime & Shale
2530	2757	Shale & Lime
2757	2838	Lime & Shale
2838	3310	Lime
3310	3360	Core
3360	3377	Lime
	3377	T.D.
		D.&A.

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1960
CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

Don Gardner
Don Gardner

Subscribed and sworn before me this 5th day of November, 1959.

My commission expires Nov. 3, 1960

Helen L. Hodgson
Helen L. Hodgson, Notary Public