

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Saline County. Sec. 19 Twp. 13 Rge. 3 (N) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NE NE

Lease Owner. Westgate-Greenland Oil Co.

Lease Name. Shank Well No. 1

Office Address. 508 Wolcott Building, Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed. Jan. 14, 19 44

Application for plugging filed. Jan. 15, 19 44

Application for plugging approved. 19

Plugging commenced. Jan. 15, 19 44

Plugging completed. Jan. 15, 19 44

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes Ruel E. Durkee

Name of Conservation Agent who supervised plugging of this well. Ruel E. Durkee

Producing formation. Depth to top. Bottom. Total Depth of Well. 3815 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	168'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole full of heavy mud to 168' of top. Drove wooden plug to bottom of surface pipe. Put in 20 sacks cement. Finished filling hole full of heavy mud within 15' of top and put in 5 sacks cement.

19 13 3W
2 7



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C. C. Nelson Drilling Company
Address. 508 Wolcott Bldg., Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

C. C. Nelson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Nelson

508 Wolcott Bldg., Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 19th day of January, 19 45

Notary Public signature

My commission expires June 22, 1945

15-169-00050-00-00

COMPANY: Westgate-Greenland Oil Co.
 CONTRACTOR: C. C. Nelson Drilling Co.
 FARM: Henry Shank #1
 LOCATION: NE NE NE Saline County
 Section 19-13-3W
 COMMENCED: December 15, 1944
 COMPLETED: January 16, 1945

0	to	90	Surface sand
90	to	555	Shale and shells
555	to	700	Lime
700	to	975	Sand and lime
975	to	1120	Shale and shells
1120	to	1270	Sandy lime
1270	to	1290	Shale
1290	to	1670	Shale and shells
1670	to	1970	Lime
1970	to	1985	Sand
1985	to	2120	Lime
2120	to	2250	Shale
2250	to	2610	Lime
2610	to	2745	Shale and lime
2745	to	2906	Shale
2906	to	2915	Mississippi lime and chert
2915	to	2965	Lime and chat
2965	to	3025	Lime
3025	to	3220	Lime and chert
3220	to	3250	Shale
3250	to	3285	Lime and shale
3285	to	3360	Shale
3360	to	3405	Lime and chert
3405	to	3428	Lime
3428	to	3440	Sand and lime
3440	to	3470	Lime
3470	to	3550	Shale
3550	to	3570	Lime
3570	to	3618	Lime and chert
3618	to	3660	Lime
3660	to	3670	Sand
3670	to	3695	Lime
3695	to	3735	Simpson sand & shale
3735	to	3745	Simpson sand
3745	to	3747	Sand
3747	to	3785	Arbuckle lime
3785	to	3815	Lime
		3815	T.D.

S.L.C. 3815 equals 3819

Set 168' of 10" surface pipe. Cemented with 90 sacks cement.

TOPS
 Kansas City 2213
 Chat 2902
 Hunton 3353
 Viola 3545
 Simpson 3655
 Arbuckle 3747
 T.D. 3815

01-22-1945

19 13 3W
 2 7
 DRY, PLUGGED AND ABANDONED

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Shank #1, Section 19-13-3W, Saline County, Kansas, as reflected by files of the C. C. Nelson Drilling Company.

C. C. Nelson

Subscribed and sworn to before me a Notary Public, within and for Reno County, Kansas, this 19 day of January 1945.

My Commission Expires June 22, 1945

Sheldon H. Gley