

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 145-39 ANG<sup>cc</sup>  
LOCATION NW 1/4 E 1/2 SE 4 NWNESE  
SEC. 20 TWP. 11 RGE. 15 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Bronson "A"

Operator Summit Oil Co. Inc. Address Box 73 Russell Kans.

Field \_\_\_\_\_ County Russell

Total Depth 3268 Feet.

Plugging Contractor Jayhawk Casing Pulling Co.

Plugging Contractor's License No. 19

Address Russell Kans.

(Describe briefly the manner in which the well was plugged)

Cable Tool

Surface Casing 18' of 20" Other Casing 7" @ 2924 w/ 100 SX Cem.  
5 1/2" @ 3147' w/ 90 SX Cem. 4 1/2" Liner 3114' - 3264' Cem.  
Fill back with chat to 3250 and dumped 5 SX Cem  
With dump bailer. Shot off and pulled 5 1/2" casing  
7" casing pulled off. Freed 7" casing and pumped  
In 25 SX of fill mud pulled 7" casing to 225' and  
pumped In 50 SX of Cem. Laid down casing mudded hole  
up to 25' set rock bridge and 10 SX Cem to surface

1-9-54

Warren H. Horner  
District Conservation Agent

Date 1-6-54

**PLUGGING**  
FILE SEC 20 TWP 11 RGE 15 W  
PAGE 145 LINE 39