

15-167-20579-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 9 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Walt Oden of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Clinton Oil Co. guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 217 N. Water, Wichita, Kansas

Lease Name: M. Albrecht Well No. # 1-V

Location: SE NW NW Sec. 7 Twp. 11 Rge. 15 (E)(W) W

County: Russell Total Depth 3543 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Walt Oden was instructed to plug the well as follows:

10 3/4" csg. 221' Cwc.

Circulated hole with heavy mud to 600' & displaced 50 sax cement thru drill pipe. Mud to 200' & displaced 30 sax cement thru drill pipe.

Mud to 30', 1/2 sax hulls, plug, & displaced 15 sax cement with Sun Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Dore L. Linn  
Conservation Division Agent