

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Oden of Red Tiger Drilg Co. has this date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Frontier Oil Co.

Complete Address: 1720 Kans State Bank Bldg, Wichita, Ks. 67202

Lease Name: Reich Well No. 1

Location: CW/2 E/2 SW/4 Sec. 21 Twp. 11 Rge. 15 (W)

County: Russell Total Depth 3378 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Oden was instructed to plug the well as follows:

Fill Hole @ Mud Spot 40' x Cement @ 540'

" " @ " " 20' x " @ 270

" " @ " " To top 5' x Halls, Plug 10' x Cement.

2' x Cement in Ret Hole

280' of 8 5/8" surface casing Cement Circ

Very truly yours,

Duane R. ...
Conservation Division Agent