

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1966
02-21-ldc
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Buckheister of John O. Farmer has this
date requested permission to plug the following described well:

Mr. John O. Farmer guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: 370 W Wichita Ave., Russell, Kansas

Lease Name: Stout Well No. # 1

Location: NE NE NW Sec. 28 Twp. 11 Rge. 15 (E)(W) W

County Russell Total Depth 3384 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dale Buckheister was instructed to plug the well as follows:

8 5/8" 151' Cwc.

Circulated hole with heavy mud to 400'; set plug; displaced 20 sax

cement thru drill pipe. Mud to 150'; set plug with 1/4 sax hulls;

displaced 20 sax cement thru drill pipe. Mud to 40'; 1/2 sax hulls;

plug & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Dore L. Truman
Conservation Division Agent