

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. NE NE SW

LOCATION NE SW

SEC. 19 TWP. 11 RGE. 16-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease C. A. Hodge

Operator Summit Oil Co., Inc. Address Bldg. 1 to an Bldg. Russell, Kans

Field \_\_\_\_\_ County Russell

Total Depth 3355- Feet.

(Describe briefly the manner in which the well was plugged)

Surface <sup>Pipe</sup> pulled out of Old Cable Tool Well  
7" casing set 3248 ft - 200 sacks of cement  
Cement Plug at 2980 ft & 2750 ft - Put in by Co.  
Hole filled with mud - 7" casing parted at 400 ft  
& pulled out - mud to 250 ft - Set rock bridge  
& 35 sacks of cement at 250 ft - mud to 30 ft  
Bridge & 15 sacks of cement at the surface  
Haystack Pipe Pulling Co.

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 23 1952

**PLUGGING**

CONSERVATION DIVISION  
Wichita, Kansas

FILE SEC 29T 11  
BOOK PAGE 10 LINE 44

C. L. Stough  
District Conservation Agent

Date 4-19-52

*FX*