

15-167-06307-0001

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 107-2  
LOCATION SE NW NE  
SEC. 29 TWP. 11 RGE. 15

Dry Hole SWD Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. SWD B-2 Lease ~~Book~~ Booth \_\_\_\_\_  
Operator Stanolind Oil & Gas Address Box 35 Gorham, Kans  
Field Fairport County Russell  
Total Depth 3212 Feet.

(Describe briefly the manner in which the well was plugged)

15" at 45' - 7" at 3016' - 5" liner from 3000' to 3200' and  
113' for 4" liner.

Filled hole with mud to 3000', set chat and 5 sax cement., pulled  
600' 7" casing, filled hole with mud to 250', set rock bridge and  
25 sax cement, filled with mud to 30', set rock bridge and 15  
sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 29 T 11 R 15  
BOOK PAGE 107 LINE 8

RECEIVED  
OCT 9 1951  
CO. 11  
DIVISION  
Wichita, Kansas  
District Conservation Agent

Date 10-4-51