

15-167-00577-0002

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 43-18
LOCATION NE NW NE
SEC. 29 TWP. 11 RGE. 15

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Booth "B"
Operator Stanolind Oil Co ^{of Gas} Address Gorham, Kans
Field Fairport County Russell
Total Depth 3265 Feet.

(Describe briefly the manner in which the well was plugged)

3 1/2" liner 65' - 6 5/8" 3110', 8 5/8" 2659'.
Filled with sand and chat to 3100', set 4 sax cement with dump
bailer, pulled 2488' 7" and 508', 8 5/8" - filled hole with
heavy mud to 250', set bridge and 25 sax cement, filled with
mud to 30', set bridge and 15 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN X 3 1951

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 12-29-50

PLUGGING
FILE SEC 29 T 11 R 15W
BOOK PAGE 43 LINE 18

N 24536