



15-167-00093-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

STATE CORPORATION COMMISSION

DEC 28 1959
D-28-1959
CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date August 14, 1959, authorized the following plugging operation:

Operator's Full Name: ~~Murfin Drilling Co.~~ John P. Habiger

AUB
LCC

Complete Address: 617 Union Center, Wichita, Kansas

Lease Name: Janousek Well No. 1

Location: NE-SW-SW Sec. 11 Twp. 13 Rge. 11 (E) (W) X

County: Russell Total Depth: 3402

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 240' with heavy mud.
Push plug and 1/4 sack hulls to 240' and cement with 20 sacks thru
drill pipe. Fill hole to 40' with heavy mud--set solid bridge--
cement with 10 sacks. Fill, bridge, and cement rathole with
2 sacks.

Very truly yours,

Signed: [Signature]
Conservation Division Agent