

15-167-36569-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Russell County. Sec. 9 Twp. 11 Rge. 15W(E) (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines. CWL SW SE

Lease Owner B & R Drilling Co.

Lease Name Shober Well No. 1

Office Address Russell, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6/18 1942

Application for plugging filed 10/25 1945

Application for plugging approved 10/25 1945

Plugging commenced 10/25 1945

Plugging completed 10/30 1945

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr

Producing formation Depth to top Bottom Total Depth of Well 3434 Feet

Show depth and thickness of all water, oil and gas formations.



OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4"	79'	None
				5 1/2"	3425'	1646', 2"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran 6 sacks cement on bottom -  
Mudded to 150' - Ran 15 sacks cement -  
Mudded to 15' - Ran 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R Drilling Co.  
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

C. L. Roberts (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) C. L. Roberts

Russell, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of October 1945

My commission expires July 2, 1949

Jenevieve Pasko Notary Public.

15-167-36569-0000

B and R Drilling Company  
Shober #1

Sec. 9 Twp. 11 Rge. 15

Total Depth: 3434'

County: Russell, Kansas

Comm: 5/27/42

Comp: 6/13/42

Casing

Cement

10-3/4"  
5-1/2"

Set at 79'  
Set at 3425'

70 sacks  
175 sacks

Formation	Depth
Surface soil, clay	20'
Sand, gravel	70'
Blue shale	77'
Shale, black	133'
Shale & shells	300'
Shale, sand & shells	545'
Lime, sand & iron streaks	600'
Sand & shale	680'
Lime, sandy	700'
Shale & shells	745'
Red bed and shells	885'
Red bed, shale & shells	1034'
Anhydrite	1071'
Blue shale, red rock & shells	1170'
Shale & shells	1330'
Shale & lime	1415'
Shale	1465'
Shale & salt	1581'
Shale & shells	1630'
Anhydrite	1670'
Anhydrite & lime, broken	1735'
Shale & shells	1755'
Lime & shale	1900'
Lime, shale, sand streaks	1965'
Lime and shale	2060'
Lime	2105'
Lime & shale	2165'
Shale	2185'
Lime	2215'
Shale	2230'
Lime	2270'
Shale	2285'
Lime	2325'
Shale & shells	2355'
Lime & shale	2515'
Shale	2580'
Lime, broken	2640'
Shale & shells	2705'
Broken lime & shale	2745'
Shale, soft & sandy	2756'
Lime, broken	2775'
Shale & lime	2835'
Lime	3050'
Shale (grey)	3064'
Lime	3275'
Shale	3288'
Lime	3290'
Lime-hard	3320'
Lime	3332'
Broken lime & shale	3340'
Lime	3365'
Lime & shale (brown)	3390'
Lime & red rock	3422'
Cherty Conglomerate	3425'
Dolomite & chert	3434'

9 11 15  
32 4

