


15-167-04547-0000

WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Russell County. Sec. 28 Twp. 11S Rge. 15 (X) (W)  
Location as "NE/CNWxSWx" or footage from lines C/ N/2 N/2 SE/4  
Lease Owner Womer Oil Co.  
Lease Name Hagaman Well No. 2  
Office Address 434 Ohio, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 20, 19 60  
Application for plugging filed April 20, 19 60  
Application for plugging approved April 20, 19 60  
Plugging commenced April 20, 19 60  
Plugging completed April 20, 19 60  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3347 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Filled hole with heavy mud to 210', 1/4 sax hulls, plug, & 25 sax cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & 10 sax cement, cementing to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1960 04-26-60  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bergman Drilling, Inc.  
Address 425 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Harold Bergman, Contractor, of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Harold Bergman  
425 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of April 19 60  
My commission expires June 30, 1963.  
Cecile L. Lawson  
Cecile L. Lawson, Notary Public.



DRILLER'S LOG

15-167-04547-0000

#2 Hagaman, C/ N/2 N/2 SE/4 28-11s-15w, Russell County, Kansas.

0-0045 Shale & Red Bed  
 45- 222 Shale & Red Bed  
 222- 470 Shale & Red Bed  
 470- 600 Sand & Red Bed  
 600- 705 Shale  
 705- 920 Shale & Red Bed  
 920- 940 Anhydrite  
 940- 965 Shale & Shell  
 965-1210 Shale  
 1210-1450 Shale Salt  
 1450-1610 Shale & Shells  
 1610-1715 Shale & Shell  
 1715-1895 Shale & Lime  
 1895-2015 Lime & Shale  
 2015-2120 Lime & Shale  
 2120-2205 Shale & Lime, Shell  
 2205-2330 Lime & Shale  
 2330-2465 Shale & Lime  
 2465-2590 Shale & Lime  
 2590-2680 Shale & Shells  
 2680-2715 Shale & Lime  
 2715-2780 Shale & Lime  
 2780-2810 Lime  
 2810-2855 Lime  
 3855-2910 Shale & Lime  
 2910-2970 Lime  
 2970-3030 Lime  
 3030-3035 Lime  
 3035-3050 Lime  
 3050-3060 Lime  
 3060-3120 Lime - Shale  
 3120-3165 Lime  
 3165-3205 Lime  
 3205-3260 Lime  
 3260-3310 Lime & Shale  
 3310-3347 Shale, Lime Chirt  
 3347 Total Depth.

Date Started: April 10, 1960  
Completed: April 21, 1960

GEOLOGICAL TOPS:

Elevation: 1852' Kelly Bushing  
 Anhydrite 920 (driller) / 932'  
 Howard 2693 - 841  
 Topeka 2721 - 877  
 Heebner 2945 -1093  
 Toronto 2964 -1112  
 Douglas 2980 -1128  
 Lansing 2996 -1144  
 Shaley Cong. 3309 -1457  
 Cherty Cong. 3329 -1477  
 Total Depth 3347 -1495

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 26 1960  
 CONSERVATION DIVISION  
 Wichita, Kansas


A F F I D A V I T

STATE OF KANSAS )  
 )  
 COUNTY OF SEDGWICK )

SS:

I, do swear that the statements and matter herein contained are true and correct to the best of my knowledge.

BERGMAN DRILLING, INC.



*Harold Bergman*  
 Harold Bergman

Subscribed and sworn to before me this 25th day of April, 1960.

*Cecile L. Lawson*  
 Cecile L. Lawson, Notary Public

My Commission Expires: June 30, 1963.