

RECEIVED

MAY 27 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME STRECKER

WELL NUMBER 1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 28 TWP. 11 RGE. 15 (R) or (W)

COUNTY RUSSELL

Date Well Completed 8-5-65

Plugging Commenced 5-22-2003

Plugging Completed 5-22-2003

LEASE OPERATOR LORENZEN OIL CO.

ADDRESS 705 1/2 AVE. G, FORT MADISON, IOWA 52627

PHONE (819) 3726665 OPERATORS LICENSE NO. 7628

Character of Well OIL

(i.e., Gas, O&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 5-22-2003 (date)

CASE MORRIS (KCC-District Agent's Name)

ACO-1 filed? NO If not, is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. _____

Give depth and thickness of all water, oil and gas formations.

LOGS: GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		230'	0'	8 5/8"		NONE
		3332'	0'	5 1/2"		NONE
		3325'	0'	2 7/8"		NONE
		3310'	875'	3/4" RODS		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from feet to feet each set.
HOOKUP TO 2 7/8" TBG. MIX DYE IN WTR TOOK 18 BBL TO CIRC 5 1/2" ANNULUS
MIX 120SKS CIRC CEMENT IN 5 1/2" ANNULUS. SHUT ANNULUS PUMP 80SKS CEMENT &
400# HULLS. PUMP 100SKS & 100# HULLS DOWN 8 5/8" ANNULUS PSI TO 300# HOLD STEADY
SHUT IN. HOOKUP TO TBG. SQUEEZE W/ 30SKS PSI TO 500# ISIP 200# ALICEMENT 60-40
POZ, 10% GELL

Name of Plugging Contractor ALLEED CEMENTING License No. _____

Address 24 S. LINCOLN, RUSSELL, KS. 67665

Name of Party Responsible for Plugging Fees: LORENZEN OIL CO.

State of KANSAS County of RUSSELL, ss.

ALLEN BANGERT (Employee of Operator) or (Operator) of well described well, being first duly sworn on oath, says: That I have knowledge of the facts and contents, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Allen Bangert

(Address) 3365 186TH STR., RUSSELL, KS. 67665

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 2003

Verna May Hutchings
Notary Public

My Commission Expires: April 10 2005

