


15-167-04549-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Russell County, Sec. 29 Twp. 11 Rge. 15W (E) (W)
Location as "NE/CNW%SW%" or footage from lines Appx. SW NE SE
Lease Owner Abbot H. C. Bennett
Lease Name Abbott Well No. 4
Office Address 1214 Union Nat'l Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 5/27 1960
Application for plugging filed 5/27 verbally 1960
Application for plugging approved 5/27 verbally 1960
Plugging commenced 5/27 1960
Plugging completed 5/27 1960
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3280 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	882'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole to 860' w/heavy mud. Push wood plug and 1/4 sack hulls
down w/drill pipe. Cemented w/25 sx. Fill hole to 40/feet base
cellar, plug w/1/4 sack hulls. Cemented w/10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1960


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL
Harold Wurst employee of drilling contractor
(employee of contractor) or (contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
By Harold Wurst BENNETT & ROBERTS DRILLING, INC.
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1960
My commission expires 6/17/62
Clara Summa Notary Public.



15-167-04549-0000

H. C. BENNETT
ABBOTT #4

Approxx. SW NE SE Sec. 29-11-15
Russell County, Kansas

RTD 3280'

CONTRACTOR: Bennett & Roberts Drilling, Inc.

Commenced 5/16/60
Completed 5/27/60

Set @ 5/8" @ 882' w/400 sx cmt

Top Soil & Post Rock	60'
Clay & Shale	100
Shale & Shells	490
Sand	515
Shale & Streaks Hard Sand	550
Shale & Sand	620
Red Bed	844
Anhydrite	905
Shale & Shells	1330
Shale & Lime	1845
Lime	2100
Lime & Shale	2635
Lime	3280

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1960

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By *James Lee Marshall*

Subscribed and sworn to before me this 1st day of June, 1960.

Clare Thomas
Notary Public

My Commission Expires 6/17/62