

4-15

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-167-22,577-0000

LEASE NAME Janne

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR H & H Production, Inc.

SEC. 31 TWP. 11 RGE. 15 ~~RE~~or (W)

ADDRESS P.O. Box 348 Russell, KS 67665

COUNTY Russell

PHONE# (913) 483-4898 OPERATORS LICENSE NO. 7124

Date Well Completed 4-15-85

Character of Well D&A

Plugging Commenced 4-15-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-15-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.  
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3464

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @3436' w/20 sacks 50/50pozmix 6% gel 3% cc. thru drill pipe  
Next Plug: @ 680' w/40 sacks " " " " " "  
Next Plug: @ 435' w/80 sacks " " " " " "  
Top Plug: @ 40' w/solid bridge of 1 sack Hulls & 10 sacks cement 10 sacks in Rat Hole  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. RECEIVED

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

STATE CORPORATION COMMISSION  
04-18-85  
APR 18 1985

Bill Draney (Employee of Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill Draney

(Address) P.O. Box 823 Great Bend, KS 67530

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 17 day of April, 1985  
Dorothy M. Blague  
Notary Public



My Commission Expires: 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: April 10, 1985  
 DATE COMPLETED: April 15, 1985

H & H Production, Inc.  
 JANNE #1  
 NW NW SE  
 Sec. 31, T11S, R15W  
 Russell County, Ks.

ELEVATION 1710 K.B.

0 - 260' Surface Soil, Post Rock, Shale  
 260 - 515' Sand & Shale  
 515 - 878' Red Bed & Shale  
 878 - 904' Anhydrite  
 904 - 2660' Lime & Shale  
 2660 - 2909' Lime  
 2909 - 2913' Shale  
 2913 - 3031' Lime & Shale  
 3031 - 3436' Lime  
 3436 - 3464' Dolomite  
 3464' RTD

FORMATION DATA

Anhydrite	878'
Topoka	2660'
Heebner	2909'
Toronto	3031'
Lansing K.C.	2958'
Case K.C.	3211'
Arbuckle	3436'
RTD	3464'

Surface Pipe: Set new 8-5/8",  
 23 @ 13639' w/325 sacks 60/40  
 pozmix 20 gel 30 cc.

A F F I D A V I T

STATE OF KANSAS  
 COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.


Bill Draney

Subscribed and sworn to before me this 17 day of April 1985.

My Comm. Expires:

4-29-86

Verahy M Hague  
 Notary Public



RECEIVED  
 STATE CORPORATION COMMISSION

APR 18 1985

CONSERVATION DIVISION  
 Wichita, Kansas