


15-167-06182-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Russell County. Sec. 31 Twp. 11 Rge. 15 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SE
Lease Owner Stearns Petroleum, Inc.
Lease Name Uhlig Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 22 1950
Application for plugging filed August 22 1950
Application for plugging approved August 22 1950
Plugging commenced August 22 1950
Plugging completed August 23 1950
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Stough, Great Bend, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	228 ft.	Circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned Pats
Circulated Hole with heavy mud to 228'
Set a rock bridge at 228'
Placed 15 sacks cement on top of bridge at 228'
Mudded hole to 30'
Set a plug and bridge at 30'
Placed 10 sacks of cement on top of bridge to top of hole

RECEIVED
CONSERVATION DIV.
AUG 28 1950
STATE CORPORATION COMMISSION
WICHITA, KANSAS
08-28-50

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Stearns Petroleum Inc.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 23rd day of August, 1950.
Harold J. Urbonek
Notary Public.

PLUGGING
FILE SEC-31 T-11 R-15
BOOK PAGE-23 LINE-45

15-167-06182-0000

UHLIG #1

Company: C. R. Holland, et al
Contractor: Stearns Petroleum, Inc.
Commencement date: 8-1-50
Completion date: 8-23-50

Location: SE NE SE, Sec. 31, T11, R15,
Russell County, Kansas

Elevation: 1766' D. F.

Casing Record:

8-5/8" 224'
cmtd w/ 125 sxs. cement

Totco:

30 min.	862'
10	1140'
10 45 min.	1493'
10	1506'
10 35 min.	1536'
10 45 min.	1567'
20	1597'
10 35 min.	1641'
10	1702'
40 min.	1733'
10 20 min.	1764'
10 15 min.	1794'
10 30 min.	1824'
10 15 min.	1872'
10 30 min.	1932'
20	2023'
20 30 min.	2236'
20 30 Min.	2329'
20	2380'
20	2432'
20	2602'
20 30 min.	2766'
20 15 min.	2855'
20 15 min.	2920'

WELL LOG

surface	0	200
shale and shells sand	20	190
shale and red rock	190	450
sand	450	550
red rock and shale	550	886
<u>Anhydrite</u>	886	903
shale and shells	903	1240
salt	1240	1460
shale and shells	1460	1640
lime	1640	1675
shale and shells	1675	1812
lime and shale	1812	2225
shale	2225	2240
shale and shells	2240	2513
lime and shale	2513	2810
lime	2810	2840
lime and shale	2840	2873
lime	2873	3272
<u>Base of Kansas City</u>	3272	
lime and shale	3272	3296
<u>Total Depth</u>		3296

RECEIVED
Conservation Div.
AUG 28 1950
STATE CORPORATION
COMMISSION
KANSAS

STATE OF KANSAS)
(SS
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

x [Signature]

SUBSCRIBED and sworn before me this 23rd day of August, 1950



PLUGGING

FILE SEC 31 T11 R15W

BOOK PAGE 23 LINE 25

[Signature]
NOTARY PUBLIC