


15-167-21131-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Russell County, Sec. 27 Twp. 13S Rge. 11 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
30' S & 150' E SW SW NW
Lease Owner Custom Oil Exploration
Lease Name Eslinger "B" Well No. 1
Office Address Box 305, Chase, KS 67524
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed 12-18 1977
Application for plugging filed 12-18 1977
Application for plugging approved 12-18 1977
Plugging commenced 12-18 1977
Plugging completed 12-18 1977
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well 3240
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	243'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Mud laden fluid 3240 to 420'
40 sks cement @ 420'
20 sks cement @ 210'
10 sks cement @ 40'
2 sks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
12-21-1977
DEC 21 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS COUNTY OF RUSSELL, ss.
Joe K. Branum (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
Box 506, Russell, KS 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1977

Patricia L. Clark
Notary Public.

My commission expires October 2, 1979



15-167-21131-00-00

EMPHASIS OIL OPERATIONS

Box 506

Russell, Kansas 67665

DRILLERS LOG

OPERATOR: Custom Oil Exploration
Box 305
Chase, KS 67524

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Eslinger "B" WELL: #1

LOCATION: 30'S & 150'E SW SW NW
Section 27-13S-11W
Russell County, Kansas

Total Depth: 3240'

Elevation: 1682' K.B.

Commenced: 12-10-77

Completed: 12-18-77

Casing: 8-5/8" @ 243'

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	246	Lime & Shale	2295
Shale & Sand	510	Shale & Lime	2532
Sand & Shale	539	Lime & Shale	2743
Anhydrite	572	Shale & Lime	2912
Shale & Sand	1085	Lime & Shale (R.T.D.)	3240
Shale & Lime	2167		

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1977
12-21-1977
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF RUSSELL) ss

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 19th day of December, 1977.

My Commission Expires: October 2, 1979.



Patricia L. Clark

Notary Public