

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-22, 346-00
326 00

LEASE NAME Star "C"

WELL NUMBER 1

SPOT LOCATION 100' N & 100' E of
NE SE NW

SEC. 19 TWP. 13 RGE. 11 (E) or (W)

COUNTY Russell

Date Well Completed 4-5-84

Plugging Commenced 4-5-84

Plugging Completed 4-5-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Kansas 67665

PHONE # (913) 483-3144 OPERATORS LICENSE NO. 5655

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	375'	Cmtd. w/240 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Spot 25 sax cement @3,400' thru 4 1/2" drill pipe, push bridge plug to 720', spot 25 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 660', spot 80 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 375', spot 40 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 40' w/1 sax hulls on plug, dump 10 sax cement on plug to cellar. Dump 10 sax cement in rat hole and 10 sax cement in mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164
Address Shields Bldg., Russell, Kansas 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

R.L. SHIELDS

CONTRACTOR
(Employee or Operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R L Shields

(Address) Shields Bldg., Russell, Kansas

RECEIVED
STATE CORPORATION COMMISSION
04-19-1984
APR 19 1984

SUBSCRIBED AND SWORN TO before me this 17 day of April, 1984

Ruth Phillips
Notary Public

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires

RUTH PHILLIPS
STATE NOTARY PUBLIC
RUSSELL COUNTY, KS.
KANSAS My App. Exp. 5-26-87

Form CP-4 1-84
Revised 06-83




Shields

15-167-22346-00-00
Russell, Kansas

WELL LOG

Operator: John O. Farmer, Inc.
 Well: Star "C" #1
 Commenced: March 28, 1984
 Completed: April 5, 1984
 Contractor: Shields Drilling Co., Inc.

Well Description: 100' North and 100' East
 of NE SE NW
 Sec. 19-13S-11W
 Russell County, Kansas



Elevation: 1,811' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	375'	Cmtd. w/240 sax

..... Figures Indicate Bottom of Formations

Post rock	40'
Post rock, clay & shale	380'
Shale	716'
Anhydrite	746'
Shale	1,380'
Shale & lime	2,965'
Lime	3,470' RTD

Notes

RECEIVED
 STATE CORPORATION COMMISSION
 APR 19 1984
 0419-1984
 CONSERVATION DIVISION
 Wichita, Kansas