

RECEIVED

JUL 08 2010

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Form ACO-1

June 2009

Form Must Be Typed

Form must be Signed

All blanks must be Filled

OPERATOR: License # 34352
Name: N-10 Exploration, LLC
Address 1: 124 N. Main
Address 2: PO Box 195
City: Attica State: KS Zip: 67009 +
Contact Person: Randy Newberry
Phone: (620) 254-7251
CONTRACTOR: License # 33902
Name: Hardt Drilling, LLC
Wellsite Geologist: Tim Pierce
Purchaser:

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil WSW SWD SIOW
 Gas D&A ENHR SIGW
 OG GSW Temp. Abd.
 CM (Coal Bed Methane)
 Cathodic Other (Core, Expl., etc.):

If Workover/Re-entry: Old Well Info as follows:

Operator:

Well Name:

Original Comp. Date: Original Total Depth:

Deepening Re-perf. Conv. to ENHR Conv. to SWD
 Conv. to GSW

Plug Back: Plug Back Total Depth

Commingled Permit #:

Dual Completion Permit #:

SWD Permit #:

ENHR Permit #:

GSW Permit #:

3/30/2010 4/8/2010 4/20/2010
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 007-23525-00-00

Spot Description: W/2 SW NE

SW NE Sec. 21 Twp. 34 S. R. 11 East West

1,980 Feet from North / South Line of Section

2,310 Feet from East / West Line of Section

Footages Calculated from Nearest Outside Section Corner:

NE NW SE SW

County: Barber

Lease Name: Medicine River Ranch Well #: A1

Field Name:

Producing Formation: Mississippi

Elevation: Ground: 1341' Kelly Bushing: 1351"

Total Depth: 4830 Plug Back Total Depth: 4788

Amount of Surface Pipe Set and Cemented at: 265 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set: Feet

If Alternate II completion, cement circulated from:

feet depth to: w/ sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content: ppm Fluid volume: 320 bbls

Dewatering method used: Hauled Off

Location of fluid disposal if hauled offsite:

Operator Name: Hart Energies, LLC

Lease Name: Marylne OWWO SWD License #: 32798

Quarter SE Sec. 2 Twp. 31 S. R. 10 East West

County: Barber Permit #: D-28, 465

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Rebecca Newberry

Title: Secy Treas Date: 7/7/2010

KCC Office Use ONLY

Letter of Confidentiality Received

Date:

Confidential Release Date:

Wireline Log Received

Geologist Report Received

UIC Distribution

ALT I II III Approved by: DLG Date: 7/9/10

RECEIVED

JUL 08 2010 Side Two

Operator Name: N-10 Exploration, LLC Case Name: Medicine River Ranch Well #: A1
Sec. 21 Twp. 34 S. R. 11 East West County: Barber

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets)
Samples Sent to Geological Survey
Cores Taken
Electric Log Run
Electric Log Submitted Electronically
List All E. Logs Run: Dual Induction, Dual Compensated Porosity

CASING RECORD Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (in O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives.

ADDITIONAL CEMENTING / SQUEEZE RECORD Table with columns: Purpose, Depth Top Bottom, Type of Cement, # Sacks Used, Type and Percent Additives.

PERFORATION RECORD - Bridge Plugs Set/Type Table with columns: Shots Per Foot, PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated, Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used), Depth.

TUBING RECORD: Size: 2-7/8" Set At: 4587 Packer At: Liner Run: Yes No

Date of First, Resumed Production, SWD or ENHR. 4/27/2010
Producing Method: Flowing Pumping Gas Lift Other (Explain)
Estimated Production Per 24 Hours: Oil Bbls. 70 Gas Mcf 220 Water Bbls. 250 Gas-Oil Ratio 3.14 - 1 Gravity 25

DISPOSITION OF GAS: Vented Sold Used on Lease
METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled Other (Specify)
PRODUCTION INTERVAL: 4614-4647

ALLIED CEMENTING CO., LLC. 037120

ATTN: P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
medicine ledge

RECEIVED

JUL 08 2010

KCC WICHITA

DATE <u>3/31/10</u>	SEC. <u>21</u>	TWP. <u>34S</u>	RANGE <u>11W</u>	CALLED OUT <u>9:00 AM.</u>	ON LOCATION <u>10:30 A.M.</u>	JOB START <u>11:00 A.M.</u>	JOB FINISH <u>11:30 A.M.</u>
MEDICINE RIVER LEASE <u>POWY A</u>		WELL # <u>1</u>	LOCATION <u>Salt Canyon Rd, E to Dead End</u>		COUNTY <u>Barber</u>	STATE <u>KO.</u>	
OLD OR <u>NEW</u> (Circle one)			<u>S+C into</u>				

CONTRACTOR Herot 1 OWNER N-10 Exploration

TYPE OF JOB Surface

HOLE SIZE 12 1/4 T.D. 700' CEMENT AMOUNT ORDERED 215 5x 60/40/2+38 1/4

CASING SIZE 8 7/8 DEPTH 265

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX 300' MINIMUM

MEAS. LINE SHOE JOINT -

CEMENT LEFT IN CSG. 20'

PERFS.

DISPLACEMENT 15 Bbls fresh

EQUIPMENT

PUMP TRUCK CEMENTER m. Coley

372 HELPER D. Franklin

BULK TRUCK

353-250 DRIVER D. Felio

BULK TRUCK

DRIVER

CEMENT AMOUNT ORDERED 215 5x 60/40/2+38 1/4

COMMON 129 5x @ 15.45 1,993.05

POZMIX 86 5x @ 8.00 688.00

GEL 4 5x @ 20.80 83.20

CHLORIDE 7 5x @ 58.20 407.40

ASC @

@

@

@

@

@

@

@

@

HANDLING 215 5x @ 2.40 516.00

MILEAGE 215 5x X 1.5 X .10 = 322.50

TOTAL 4,010.15

REMARKS:

pipe on bottom, to leak Circ. Pump 3 fresh. mix 215 5x 60/40/2+38 1/4. Release plug. Dip 15 Bbls. Shut in. Cement did Circ

SERVICE

DEPTH OF JOB 265'

PUMP TRUCK CHARGE 1018.00

EXTRA FOOTAGE @

MILEAGE 15 @ 7.00 105.00

MANIFOLD @

@

@

TOTAL 1,123.00

CHARGE TO: N-10 Exploration

STREET

CITY STATE ZIP

PLUG & FLOAT EQUIPMENT

3 3/8
1-wooden plug @ 68.00 68.00

1-Basket @ 161.00 161.00

@

@

@

TOTAL 229.00

SALES TAX (If Any)

TOTAL CHARGES 1,123.00

DISCOUNT 0.00 IF PAID IN 30 DAYS

PRINTED NAME Scott C Adairhead

SIGNATURE Scott C Adairhead

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

ALLIED CEMENTING CO., LLC. 041482

P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Medicine Lodge, KS

DATE <u>040810</u>	SEC. <u>21</u>	TWP. <u>34s</u>	RANGE <u>11w</u>	CALLED OUT	ON LOCATION	JOB START <u>11:00Am</u>	JOB FINISH <u>2:00Am</u>
LEASE <u>Medicine River Ranch</u>	WELL # <u>A-#1</u>		LOCATION <u>Medicine Lodge, S to Scott Canyon Park</u>	COUNTY <u>Barber</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one) <u>NEW</u>			<u>Rd, E to dead End, S & E into</u>				

RECEIVED
JUL 08 2010
KCC WICHITA

CONTRACTOR Hardt #1 OWNER: N-10 Expl. LLC

TYPE OF JOB Production Casing
HOLE SIZE 7 7/8 T.D. 4830
CASING SIZE 5 1/2 DEPTH 4828
TUBING SIZE DEPTH
DRILL PIPE DEPTH
TOOL DEPTH
PRES. MAX 1200 MINIMUM ---
MEAS. LINE SHOE JOINT 42.88
CEMENT LEFT IN CSG. 43'
PERFS.
DISPLACEMENT 117% Bbls 2% KCl Water

CEMENT AMOUNT ORDERED 40 sx 60:40:4% gel + 4% SMS, & 150sx "H" + 10% salt + 5# KCl-seal, & 15gal clasp & 500gals ASF

COMMON	<u>24sx</u>	@	<u>15.45</u>	<u>370.80</u>
POZMIX	<u>13sx</u>	@	<u>8.60</u>	<u>104.00</u>
GEL	<u>2sx</u>	@	<u>20.80</u>	<u>41.60</u>
CHLORIDE		@		
ASC		@		
Class "H"	<u>150sx</u>	@	<u>21.10</u>	<u>3,165.00</u>
SCIT	<u>15sx</u>	@	<u>12.00</u>	<u>180.00</u>
Kcl-seal	<u>250#</u>	@	<u>.89</u>	<u>667.50</u>
SMS	<u>14#</u>	@	<u>2.45</u>	<u>34.30</u>
KCl	<u>15gal</u>	@	<u>31.25</u>	<u>468.75</u>
ASF	<u>500gal</u>	@	<u>1.27</u>	<u>635.00</u>

EQUIPMENT
PUMP TRUCK CEMENTER Drelia
360-302 HELPER S. Paddy
BULK TRUCK
364 DRIVER M. Thimesch
BULK TRUCK
DRIVER

HANDLING 190 sx @ 2.40 456.00
MILEAGE 190 X 15 X .10 = 312.00
TOTAL 6434.95

REMARKS:

Pipe on Bttm, Break Circ., Pump Plug Flush, Plug Rat Hole w/ 15 sx 60:40 cement Mix. 25sx Scavenger Cement Mix 150sx toy Cement Stop Pump, Wash Pump & Lines, Release Plug, Start Disp w/ 2% KCl Water, See Steady increase in PST, Slow Rate Pump Plug at 117% Bbls total Disp, Release PST, Floor D, Hold

SERVICE

DEPTH OF JOB	<u>4828</u>		
PUMP TRUCK CHARGE			<u>2011.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>15</u>	@	<u>7.00</u> <u>105.00</u>
MANIFOLD	<u>Head Rental</u>	@	<u>n/c</u>

TOTAL 2,116.00

CHARGE TO: N-10 Expl. LLC
STREET _____
CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

1-TRP	@	<u>43.00</u>	<u>43.00</u>
1-AFU insert	@	<u>112.00</u>	<u>112.00</u>
1-Guide Shoe	@	<u>101.00</u>	<u>101.00</u>
8-Recip. Scatchers	@	<u>30.00</u>	<u>240.00</u>
6-Centralizers	@	<u>35.00</u>	<u>210.00</u>

TOTAL 706.00

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____
TOTAL CHARGES 2,116.00
DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME TIM PIERCE
SIGNATURE Tim Pierce