



15-167-20620-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
08-17-1973  
AUG 17 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Capital Oil Corp. guarantees payment of the plugging fee.

Operator's full Name: Capital Oil Corporation

Complete Address: 250 N. Rock Road, Wichita, Kansas

Lease Name: Thielen Well No. # 1

Location: SW NW <sup>SE</sup> NE Sec. 26 Twp. 13 Rge. 12 (E)(W) W

County: Russell Total Depth 2919 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Fred Cameron was instructed to plug the well as follows:

8 5/8" csg. 294' Cwc.

Circulated hole with heavy mud to 400', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 280' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don Truman  
Conservation Division Agent