



15-167-20619-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 27 1973  
08-27-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. James B. Devlin guarantees payment of the plugging fee.

Operator's full Name: Jayhawk Oil Company

Complete Address: 240 Sutton Place, Wichita, Kansas

Lease Name: Garrett Well No. # 2

Location: SW NE  
NE SE SW Sec. 26 Twp. 13 Rge. 12 (E)(W) W

County: Russell Total Depth 2950 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Fred Cameron was instructed to plug the well as follows:

8 5/8" csg. 281' Cwc.

Circulated hole with heavy mud to 400', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 280' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Allied Cementing Company's pump truck, cementing to base of

cellar.

Very truly yours,

Don Truman  
Conservation Division Agent