



15-167-20284-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 29 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 01-29-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Selv. Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Koch Exploration Co. guarantees payment of the plugging fee.

Operator's full Name: Koch Exploration Company

Complete Address: Box 2256, Wichita, Kansas

Lease Name: Theilen Well No. # 1

Location: NE SE NW Sec. 26 Twp. 13 Rge. 12 (E)(W) W

County: Russell Total Depth 3250 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Selv. Fickel was instructed to plug the well as follows:

8.5/8" 280' Cwc.

Circulated hole with heavy mud to 480', set plug, & displaced 40 sax

cement thru drill pipe. Mud to 270' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement

with Halliburton Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Donne L. Luman
 Conservation Division Agent