

15-167-19212-0001

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas

RCW
KCC
02-17-54

FILE NO. 10-39

LOCATION NW-SE-SW

SEC. 32 TWP. 11 RGE. 15W

Old Cable Tool

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 2 Lease Booth

Operator S.B. Barnes et al Address P.O. Box 873 Kellogg Texas

Field _____ County Russell

Total Depth 3172 Feet.

Plugging Contractor Jayhawk Casing Pulling Co.

Plugging Contractor's License No. 19

Address Russell Kans.

(Describe briefly the manner in which the well was plugged)

Casing as follows 8 5/8" @ 2563' 7" @ 2833 5 1/2"
@ 3102. Top of 7" pipe at 2865'. Filled back to 2850'
and dumped 5 sk Cem. Shot off and pulled
5 1/2" casing. 7" pipe was into at about 500'
Started this pipe and pumped in 20 sk of fresh
mud. Pulled 7" to 200' and pumped in 50 sk
of Cem. Pulled rest of 7" and 135' of 8" Filled
hole with mud to 30' set rock bridge and 20 sk Cem.

Warren D. Garner
District Conservation Agent

Date 2-15-54

PLUGGING
FILE SEC. 32 T. 11 R. 15W
BOOK PAGE 10 LINE 39