

15-167-20309-0000R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Market
Wichita, Kansas 67202

API Number 15 -

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1976

05-23-76

CONSERVATION DIVISION
Wichita, Kansas

(of this well)

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Bldg. Russell, Ks. 67665

Lease Name Eulert "A" Well No. 4

Location N/2 SENE Sec. 34 Twp. 11 Rge. 15 (W) X

County Russell Total Depth 3270

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Shields Oil Producers, Inc.

Address Shields Bldg. Russell, Ks 67665 License No. _____

Operation Completed: Hour 12⁰⁰ PM Day 21 Month 5 Year 1976

The above well was plugged as follows:

Squeezed thru 5 1/2" casing @ 15x Halls 255x Cem,
255x Mud Gel, Plug & 655x Cement. - Max Pres 1100# Shut in @ 400#
Squeezed Between 8 5/8" surface casing & 5 1/2" casing @ 355x
Cement Max Pres 600# Shut in Pres. 600#
No Perforations. - Squeezed @ 515 @ 1505x Cement. -
3263' of 5 1/2" casing cemented @ 1005x Cement. -
250' of 8 5/8" surface casing cement circ

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/27/76

INV. NO. 3272-W

Signed: Dwain Rankin
Well Plugging Supervisor