

15-167-03874-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 27-40

LOCATION NE-SE-NW

SEC. 34 TWP. 11 RGE. 15W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease O.C. Eulert

Operator The Texas Co Address 614 Bitting Bldg. Wichita Kans.

Field _____ County Russell

Total Depth 3245 Feet.

Plugging Contractor Jayhawk Casing Pulling Co.

Plugging Contractor's License No. 19

Address Russell Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4" @ 328' c.w.c. Oil string 7" O.D.
@ 3050' w/125 cc cem. L.W.P. @ 2654 top plug
2643' Filled back with sand to 2630' and
dumped 5 cc cem. shot off and pulled 7" casing
filled hole with mud to 300' set rock bridge
and run 25 cc cem with dump bucket. mud
to 30' r. bridge and 15 cc cem to base
of collar

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1954

CONSERVATION DIVISION
Wichita, Kansas

Warren H. Horner
District Conservation Agent

Date April 23, 1954

PLUGGING
FILE SEC. 34 TWP. 11 R. 15W
BOOK PAGE 22 LINE 40