


15-167-00280-0000

RECEIVED
STATE CORPORATION COMMISSION
RCWD
NOV - 5 1955
11-05-55
CONSERVATION DIVISION
Wichita, Kansas

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 11-38
LOCATION NW-5W-5E
SEC 34 TWP. 11 RGE. 15W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Eulerst.

Operator P. J. Strindhelm Address Box 363 Russell, Kans.

Field _____ County Russell

Total Depth 3210' Feet.

Plugging Contractor Mills Casing Pulling Co.

Plugging Contractor's License No. 12

Address Box 711 Great Bend, Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 763' c.w.c. 500 sq. 4 1/2" set @
3210' cem. up 150 sq. Drilled cem. to 3169'. Top
perforation 2848'. Chok back to 2830' & 4 sq. cem.
up. dump bailer. Mud to 275' from top, set plug,
rock bridge & 20 sq. cem. up. bailer. Then mud
to 35' from top, set plug, rock bridge & 10 sq.
cem. to base of cellar.

PLUGGING
FILE SEC 34 T 11 R 15W
BOOK PAGE 11 LINE 38

Milton Edwards
District Conservation Agent

Date 11-4-55