

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC - 8 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 051 - 21,408 - 0000 (of this well)

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Kansas

Lease Name Richmond Well No. 1

Location NW NE NE Sec. 7 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3477'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Helberg Drlg.

Address Morland, Kansas License No.

Operation Completed: Hour 4:45 P Day 6 Month 12 Year 1977

The above well was plugged as follows:

RTD 3477' 8 5/8 csg set 210' cwc 150 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy-mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ken Massey
Well Plugging Supervisor

INVOICED

DATE 12-8-77

INV. NO. 6325-4