

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Russell County, Sec. 13 Twp. 13S Rge. 12 (E)W (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner James D. Mooneyham & R.P. Nixon Operations, Inc.

Lease Name Cooper Well No. 1

Office Address Box 6, Beverly, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2-4-67 19

Application for plugging filed 3-15-67 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed 2-4-67 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truam

Producing formation Depth to top Bottom Total Depth of Well 3572 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	266'	8 5/8"	266'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 250' with 1/4 sack hulls and 25 sacks cement.
Top plug at 40' with 1/2 sack hulls and 10 sacks cement.
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1967
03-20-1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Vaughan Drilling, Inc.

Address 1618 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Donald D. Vaughan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Donald D. Vaughan

1618 Wichita Plaza, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 15th day of March 1967

My commission expires September 28, 1968

Donna L. Podolak Notary Public.



WELL LOG

COMPANY JAMES D. MOONEYHAM & R. P. NIXON
 OPERATIONS, INC.
 CONTRACTOR VAUGHAN DRILLING, INC.
 FARM # 1 Cooper
 LOCATION C SE SE Sec. 13-13S-12W
 Russell County, Kansas
 ELEVATION 1788 KB
 SURFACE PIPE 8 5/8" cemented at 266' Pozmix sunset
 PRODUCTION D & A
 COMMENCED 1-27-67
 COMPLETED 2-4-67

<u>FORMATION</u>	<u>DEPTH</u>
post rock	75
shale & sand streaks	266
shale	277
hard sand	289
shale, shells & sand	390
shale & sand streaks	490
red bed	672
Anhydrite	706
red bed, shale & shells	900
shale & shells	1315
shale w/sandy lime streaks	1390
shale & lime	1695
lime & shale	1998
shale & shells	2400
lime & shale	2736
lime	3040
lime & chert	3080
lime	3255
lime & shale	3325
lime, shale & chert	3572

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 20 1967
 03-20-1967
 CONSERVATION DIVISION
 Wichita, Kansas

SAMPLE TOPS

Topeka	2642
Heebner	2842
Lansing	2925
Base/Kansas City	3203
Conglomerate	3293
Viola	3395
Simpson	3506
Arbuckle	3526
RTD	3572

A F F I D A V I T


STATE OF KANSAS
COUNTY OF SEDGWICK

I, DONALD D. VAUGHAN, of the VAUGHAN DRILLING, INC., being first duly sworn on oath, state that I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan
 Donald D. Vaughan, President

Donna L. Podolak
 Donna L. Podolak, Notary Public

Subscribed and sworn to before me this 15th day of March, 1967.



My commission expires September 28, 1968.