

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Russell County. Sec. 26 Twp. 13S Rge. 12W (XX) (XXX)

Location as "NE/CNW/SW" or footage from lines SW NE SW
Lease Owner Jayhawk Oil Company
Lease Name Garrett Well No. 2
Office Address 240 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 22, 19 73
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced August 22, 19 73
Plugging completed August 22, 19 73
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2,950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	281'	None

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1973
08-30-1973
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 2,950 feet (rotary total depth) to 400 feet. Set plug at 400 feet and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 400 feet to 280 feet. Set plug at 280 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud from 280 feet to 40 feet. Set solid plug at 40 feet and cemented to cellar with 10 sacks cement, two sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dean Britting, Agent (Employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 28th day of August, 19 73

Elsie Willison
Elsie Willison Notary Public.

My commission expires June 30, 1974



KANSAS GEOLOGICAL SOCIETY 15-167-20619-00-00
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Jayhawk Oil Company**
 FARM **Garrett** NO. **2**

SEC. **26** T. **13S** R. **12W**
 LOC. **SW NE SW**

TOTAL DEPTH **2,950'**
 COMM. **August 17, 1973** COMP. **August 22, 1973**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Russell**

KANSAS



CASING
 20 10
 15 8-5/8" 281' set w/175 sxs cement
 12 6
 13 5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock	90'
Shale and Sand	283'
Shale and Shells	330'
Sand and Shale	719'
Anhydrite	756'
Shale and Shells	1,045'
Red Bed, Shale and Shells	1,475'
Shale and Lime	1,930'
Lime and Shale	2,165'
Shale and Lime	2,585'
Lime and Shale	2,690'
Lime	2,950'
Rotary Total Depth	2,950'

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 30 1973
 08-30-1973
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting


 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 28th. day of August, 1973/

Elsie Willison

 Elsie Willison - Notary Public



My Commission Expires:
 June 30, 1974