


15-167-20439-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Russell County. Sec. 26 Twp. 13S Rge. X(B) 12 (W)
Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Pickrell Drilling Company
Lease Name Thielen "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Aug. 2 19 70
Application for plugging filed Aug. 2 19 70
Application for plugging approved Aug. 2 19 70
Plugging commenced Aug. 2 19 70
Plugging completed Aug. 2 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 400' w/50 sacks, plug @ 210' w/25 sacks, plug @ 40' w/10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1970
CONSERVATION DIVISION
Wichita, Kansas
08-07-1970


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill J. Porter (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill J. Porter
Bill J. Porter
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 5th day of August, 1970



Esther Lamone
Esther Lamone
Notary Public.

My commission expires January 19, 1973

15-167-20439-00-00

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 7/24/70

Rotary Drilling Completed 8/2/70

LOCATION: Thielen "A" No. 1, SE NW NE Section 26-13S-12W
Russell County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 10 Jts. 8-5/8" surface casing set @ 208' KB. Cemented with 140 sacks cement. Completed 5:00 P.M. July 24, 1970. Circulated.

No oil string run. D & A, Plugged 10:30 A.M. August 2, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>C.F.S.</u>
209	Shale - Lime - Sand	2280
468	Shale & sand streaks	2360
685	Shale - Sand	2740
723	Anhydrite	2890
1170	Shale & Shells	2906
1420	Shale & Lime w/Lime Streaks	2914
1795	Lime & Shale	2926
2280	Shale & Lime	2970
2360	Sand & Shale	2984
2495	Shale	3260
2725	Shale & Lime	3270
2890	Lime & Shale	3300
3215	Lime	
3285	Lime & Chert	
3300	Lime, RTD	

Slope Tests

2000
2500
3000

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1970
CONSERVATION DIVISION
Wichita, Kansas

08-07-1970

The undersigned, Bill J. Porter, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By Bill J. Porter Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 14th day of August, 1970, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared Bill J. Porter, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Esther Lamone Notary Public