

15-051-00945-0000

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

County. Sec. 8 Twp. 11 Rge. 16 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines SW SW SE

Lease Owner Tomlinson & Kathol, et al

Lease Name Craig Well No. 1

Office Address Union Center Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-5 19 56

Application for plugging filed 12-5 19 56

Application for plugging approved 12-5 19 56

Plugging commenced 12-5 19 56

Plugging completed 12-5 19 56

Reason for abandonment of well or producing formation Non-productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3442 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	307	8 5/8"	307	None - Cement Circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 300'. Plug at 300'. One-half sack hulls. Twenty sacks cement.
Mud to 40'. Plug at 40'. One-half sack hulls. Ten sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1956
CONSERVATION DIVISION
Wichita, Kansas
RCWD
12-18-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mallonee Drilling Company, Inc.

Address Union Center Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Contractor

R. E. Mallonee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Mallonee

Union Center Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of December, 1956

My commission expires July 27, 1960

Ginny Harrison
Ginny Harrison, Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1956
CONSERVATION DIVISION
Wichita, Kansas
RCWD
12-21-56

PLUGGING
FILE SEC 8 T. 11 R. 16w
BOOK PAGE 123 LINE 42



15-051-00945-0000

DRILLERS' LOG
#1 Craig
SW SW SE Sec. 8-11S-16W
Ellis County, Kansas

OPERATOR: Tomlinson & Kathol
CONTRACTOR: Mallonee Drilling Company, Inc.

Commenced: 11-23-56
Completed: 12-5-56

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>	<u>REMARKS</u>
0	45	Surface soil & clay	
45	75	Post rock	
75	85	Sand	
85	307	Shale & shells	8 5/8" casing set at 307' with 225 sacks Posmix & 1 sack calcium chloride. Cement circulated.
307	400	Shale & shells	
400	560	Sand	
560	575	Sand & shale	
575	605	Sandy shale	
605	675	Sand	
675	780	Sand, shale & red bed	
780	845	Shale & red bed	
845	1017	Red bed	
1017	1050	Anhydrite	
1050	1260	Shale & shells	
1260	1520	Shale	
1520	1600	Shale & shells	
1600	1815	Shale & lime	
1815	1990	Shale & shells	
1990	2055	Lime	
2055	2280	Shale & lime	
2280	2355	Lime	
2355	2500	Lime & shale	
2500	2670	Shale & shells	
2670	2790	Shale & lime	
2790	3446	Lime	
3446	Total depth of hole		D & A

I certify that to the best of my knowledge and belief, the above represents a true and accurate Drillers' Log record of the captioned well.

R. E. Mallonee
R. E. Mallonee

State of Kansas)
) ss.
County of Sedgwick)

Subscribed and sworn to before me this _____ day of December, 1956.

My commission expires:

PLUGGING
JULY 27, 1960
8-11-R16W
BOOK PAGE 123 LINE 42

Ginny Harrison, Notary Public